

AD-A036 488

BELL HELICOPTER TEXTRON FORT WORTH TEX
IMPROVED LINEAR ACTUATOR, OH-58A HELICOPTER.(U)
SEP 74 C V HARVEY

F/G 9/5

UNCLASSIFIED

206-099-452

USAAVSCOM-TR-77-11

DAAJ01-72-A-0015


NL

| OF |
ADA036488



END

DATE
FILMED
3-77



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

ADA036488

USAAVSCOM
REPORT - TR 77-11

**IMPROVED LINEAR ACTUATOR, OH-58A
HELICOPTER**

**C. V. Harvey
BELL HELICOPTER COMPANY
POST OFFICE BOX 482
FORT WORTH, TEXAS 76101**

16 September 1974

Final Report



**APPROVED FOR PUBLIC RELEASE
DISTRIBUTION UNLIMITED**

Prepared for

**U.S. ARMY AVIATION SYSTEMS COMMAND
Maintenance Engineering Division
Post Office Box 209
St. Louis, MO 63166**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER 18 USAAVSCOM TR77-11	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) 6 IMPROVED LINEAR ACTUATOR, OH58A HELICOPTER	5. TYPE OF REPORT & PERIOD COVERED 9 Final rept.	
7. AUTHOR(s) 10 C.V./Harvey	6. PERFORMING ORG. REPORT NUMBER 14 206-099-452	8. CONTRACT OR GRANT NUMBER(s) 15 DAAJ01-72-A-0015(P2E)
9. PERFORMING ORGANIZATION NAME AND ADDRESS X Bell Helicopter Company Textron, P.O. Box 486 Ft. Worth, TX 76101	10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS DA Form 3149R DI-P-1800	
11. CONTROLLING OFFICE NAME AND ADDRESS US Army Aviation Systems Command P.O. Box 209, ATTN: DRSAV-FEL St. Louis, MO 63166	12. REPORT DATE 10 16 Sep 74	13. NUMBER OF PAGES 7
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Commander US Army Bell Plant Activity P.O. Box 1605 Ft. Worth, TX 76101 12 11p	15. SECURITY CLASS. (of this report) UNCLASSIFIED 15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES This report presents the results of Product Improvement Task 72-10		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Ball Retainer, Output Shaft, Cover, Lubrication, Reliability		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report presents the results of Product Improvement Program, Task No 72-10, wherein the engine Nil linear actuator, P/N 206-062-721-1, as installed on the OH58A helicopter, was modified for the purpose of providing better field reliability. One prototype unit was built and briefly flight tested on an OH58 helicopter. A		

UNCLASSIFIED

05H 200



BELL HELICOPTER COMPANY

POST OFFICE BOX 482 • FORT WORTH, TEXAS 76101 A **Textron** COMPANY

TECHNICAL DATA

BY C. V. Harvey DATE 9/16/74
CHECKED _____ DATE _____
APPROVED _____ DATE _____
APPROVED [Signature] DATE 9/16/74

MODEL OH-58A

NO. OF PAGES 7

REPORT NO. 206-099-452 DATE 9-16-74

TITLE IMPROVED LINEAR ACTUATOR, OH-58A
HELICOPTER

PREPARED UNDER CONTRACT DAAJ01-72-A-0015(P2E)

ACCESSION TAG	
NTIS	White Section <input checked="" type="checkbox"/>
G C	Buff Section <input type="checkbox"/>
UNANNOUNCED	<input type="checkbox"/>
JUSTIFICATION	
BY	
DISTRIBUTION/AVAILABILITY CODES	
Dist.	AVAIL. BTH. OF SPECIAL
<u>A</u>	

DISTRIBUTION STATEMENT A

Approved for public release;
Distribution Unlimited

SEP 18 1975
RECEIVED

PROPRIETARY RIGHTS NOTICE

These data are furnished with unlimited data rights to the
U.S. Government in accordance with the provisions of
Contract No. DAAJ01-72-A-0015

TABLE OF CONTENTS

	PAGE
SUMMARY	1
DISCUSSION.	2
RECOMMENDATIONS	4
APPENDIX.	4
IOM 80:BCM:wc-2753	6

SUMMARY

This report presents the results of Product Improvement Program, Task No. 72-10, wherein the engine governor NII linear actuator, P/N 206-062-721-1, as installed on the OH-58A helicopter, was modified for the purpose of providing better field reliability. The program in general consisted of the following:

1. Based on previous records and experience related to overhauled actuators, recommended changes to obtain better reliability in service were defined.
2. Based on the recommendations, preliminary drawings were made and submitted to AVSCOM.
3. One prototype unit reflecting these changes was built and installed on a bailed OH-58A located at BHC.
4. A brief flight test on the prototype unit was conducted and the unit thereafter was shipped to AVSCOM for disposition.

It is anticipated that Army service testing of this unit will prove that the subject modifications will provide sufficient increase in service life to warrant production incorporation. It is therefore concluded that the requirements of Contract No. DAAJ01-72-A-0015(P2E), Delivery Order No. 8, under which this program was conducted have been satisfactorily fulfilled.

DISCUSSION

This program was initiated when discussions between BHC, AVSCOM, and Globe Industries personnel were conducted for the purpose of defining the specific items that were relatively unreliable on the existing OH-58A Engine N_{II} Governor Linear Actuator, P/N 206-062-721-1. During these discussions, specific changes to provide for better reliability were formulated. It was agreed that Globe Industries, the manufacturer of the actuator, would incorporate changes as possible to a prototype unit and accordingly submit the associated drawings reflecting these changes. This was done. The specific parts that were redesigned are as follows:

1. Ball Retainer

Ball Retainer, P/N 35DG97, was replaced with ball retainer, P/N 35D716, in an attempt to eliminate failures of this part due to over-torquing of the output shaft. During field adjustment of the shaft rod end the jam nut must be loosened. The shaft has wrenching flats which are not held securely by field personnel. While loosening the jam nut, the output shaft rotates to the degree that the torquing action indents the ball retainer by compression action of the ball against the retainer groove. In many cases the ball tears through the side of the ball retainer, thus locking the output shaft and causing the actuator to fail to operate. If the ball merely indents the ball retainer, then the future operation of the actuator is impaired by the snagging effect of the ball in the damaged retainer. BHC over-haul records show that of the actuators overhauled, 100% of these retainers had to be replaced. This single item was found to be the major contributing cause of all actuator failures.

The material was changed from 430 stainless steel to type SAE 01 oil hardening tool steel. The new material can now be through-hardened to Rockwell C60-63, as opposed to case hardening by nitriding to a depth of .001-.002 inches on the original part. In addition, the thickness has been increased from .125 to .250 inches making possible use of larger steel balls. Since the new material in the heat treated condition has a tensile strength in the range of 300,000 psi along with increased cross section, the resistance to over-torquing of the output shaft is greatly increased.

2. Ball

The ball that rides in the retainer, P/N 66A161, identified in Item 1 above has been changed in size from .0937 to .1250 inches in diameter to accommodate the new larger retainer groove. Ball to groove contact point size, therefore, has been slightly increased.

3. Output Shaft

The output shaft, P/N 7A3908, has been changed in that the ball indents have been increased to accommodate the larger balls.

DISCUSSION (CONT'D)

4. Housing

A minor change in the housing, P/N 4D2692, is required in order to accommodate the thicker ball retainer. A thickness of .625 inch can be machined during overhaul from existing castings, or the die cast mold can be changed to make the part to the new dimension. This machining was accomplished on the prototype unit.

5. Cover

The change in the cover, P/N 2A997, concerns relocation of the marking information for maximum visibility after the actuator has been installed on the engine. Also, the torque caution note originally stamped on the output shaft, has been moved to the cover for improved visibility and permanence.

The stroke adjustment instructions have been reworded slightly for improved clarity, and the type size has been increased by a factor of approximately 3 for ease of reading. In addition, an important warning note has been stamped in red ink. Part number information has been relocated to the side of the actuator that is adjacent to the engine when the actuator is installed.

6. Lubrication

All gears as well as the output shaft guide assembly in the new actuator have been lubricated with a high temperature Mil Spec grease. The same is true for the cam washers in the stroke adjusting assembly. The old lube, Shell Oil Co. Aero Shell No. 7 per MIL-G-23827, meets a temperature range of -100° to $+250^{\circ}$ F. The new grease is Aero Shell No. 16 per MIL-G-25760 and is suitable for operation between -65° and $+400^{\circ}$ F.

This change is expected to eliminate sticking of the cam drive washers due to dried and caked grease as noted on several actuators returned from field use. In oven tests conducted as part of this investigation, the new grease remained soft and retained most of its oil after 15 hours at $+336^{\circ}$ F. Under the same conditions, the old grease became dry, hard and discolored.

RECOMMENDATIONS

If service evaluation shows the modifications made as discussed in this report satisfactorily increase the service life of the actuator it is recommended that these changes be incorporated via ECP action. Further, it is recommended that in order to maintain proper control when a unit is created at the factory or modified at overhaul, a dash number change be made for identification purposes. In addition, it is believed that the red warning note placed on the actuator cover should be changed to black lettering and the word "Warning" removed.

Appendix

Enclosed in this report is an Appendix wherein the results from flight testing of the actuator are reported by the BHC Experimental Flight Test Facility. This report shows that all results were satisfactory.

APPENDIX

BELL HELICOPTER COMPANY

Inter-Office Memorandum

5 June 1974
80:BCM:wc-2753

Memo to: Mr. C. V. Harvey

Copies to: Messrs. J. Gilday, W. McKinney, R. Schwalbach

Subject: EVALUATION OF IMPROVED LINEAR ACTUATOR INSTALLED ON
MODEL OH-58A HELICOPTER

Reference: (a) Organizational Maintenance Manual TM
55-1520-288-20

Introduction

In response to U.S. Army PIP Task No. 72-10, an improved linear actuator for the NII governor control system on the Model OH-58A helicopter was evaluated. This improved linear actuator, P/N 206 HA-161-1, contained several internal improvements for better reliability. A redefinition and re-evaluation of the printed instructions on the improved linear actuator was made to simplify the installation and adjusting procedures.

Test and Results

The improved linear actuator was installed on Model OH-58A Helicopter, S/N 42126. The actuator was rigged in accordance with the instructions in Reference (a). A test flight was made and a normal adjustment of the actuator rod length was made to compensate for this particular engine and actuator installation.

A total flight time of 0.3 hr. was flown on 27 May 1974, during which all phases of the normal flight regime were investigated. There were no abnormal characteristics of the 206 HA-161-1 linear actuator noted or any differences from normal helicopter operation with the standard 206-062-721-1 linear actuator.

Conclusions

From this investigation it was concluded that the installation, rigging and operation of the improved linear actuator was satisfactory.

Approved by:

W. E. Jennings
Chief Flight Test Engineer

B. C. Martin
Flight Test Engineer
Ext. 4822

DISTRIBUTION LIST

Power Plant Group	1
206 Project	1
Electrical Group	1
Library	1
AVSCOM	1